Company Experience

RAG Process LLC
20927 Roxette Court, Humble TX 77339 USA
Office: 346-988-1127
sales@rag-engineering.com
www.rag-engineering.com

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
1	JT - Plant	Design selection, procurement & Supply	5 MMSCFD-JT Plnats	Petrochawk Energy Corp Texas	2010
2	Fuel Gas Conditioning Skid	Design selection, procurement & Supply	5 MMSCFD Fuel Gas Conditioning Skid	Petrochawk Energy Corp Texas,Eagle Ford Shale -USA	2010
4	Gas Conditioining	Design selection, procurement & Supply	20 MMSCFD Fuel Gas Conditioning Facilities	Good Hope Refinary Louisiana - USA	2010
5	Glycol Dehydration Unit	Design selection, procurement & Supply	Capacity 15 MMSCFD gas with final outlet moisture content of 5-7 lb of water/MMSCFD. Design Pressure 1000 Psig Design Temperature 200 F	Petrochawk Energy Corp Texas	2011
6	Metering Skid	Engineering, procurement, fabrication and supply	50 MMSCFD gas Capacity metering station. Includes Daniel Gas Chromatography, Moisture analyzer, Floboss, Daniel senior orifice meter with Barton 3 Pen Chart Recorder	Quanton Resources LLC Jay, FL- USA	2011
7	Flare System	Engineering, procurement, fabrication and supply	Flare Knock out Drum,Submersible pump,Level Transmitter,Retractable type fllare burning assembly with control panel	Colombia Petrochemical	2011
8	Natural Gas Compression System (QTY) 6	Design selection, procurement & Supply	Capacity 50-60 MMSCFD Gas, Inlet Pressure 1000 Psig, Discharge pressure 1250 psig, Dresser rand natural gas compressors,Waukesha natural gas engines, Gas coolers, Oil coolers, Radiators, Suction scrubber Bottles, Discharge bottles.	Monclova Pirineos Gas SA de CV Mexico	2011
9	Condensate Storage and Metering system	Engineering, procurement, fabrication and supply	Capacity 1000 barrels, design Pressure 14.7 Psig, Design temperature 200 F. Includes: Condensate storage tanks,Condensate metering pumps, Condensate loading arms.	Falcon EDF, Ltd / True Oil, LLC ND/USA	2011
10	Three Phase Separator	Engineering, procurement, fabrication and supply	Three Phase Production Separator: Capacity 50 MMSCFD, Design Pressure 750 Psig, Design temperature.	Monclova Pirineos Gas SA de CV Mexico	2011
11	Sour Water System	Engineering, procurement, fabrication and supply	Sours water system: Design Pressure 150 Psig, Design temperature 200 F. Includes: Sour water flast Drum, Sour water exchanger, Sour water stripper reboiler.	Monclova Pirineos Gas SA de CV Mexico	2011
12	Water Transfer System	Engineering, procurement, fabrication and supply	Water Transfer System: Capacity 150 Barrel/day. Includes: 150 barrel/day water storage tank, Cetrifugal type water transfer pump.	Monclova Pirineos Gas SA de CV Mexico	2011
13	Instrument Air System	Design selection, procurement & Supply	Instrument Air Syatem Capacity 105 SCFM design Pressure 150 Psig, Design temperature 200 F. Includes: Screw type instrument air compressor,Wet air Reciever, Desiccant air dryer, Dry air reciever.	J-W Gathering Company Froerspm, LA- USA	2011
14	Fuel Gas Conditioning Skid	Design selection, procurement & Supply	Fuel Gas conditioning Skid Capacity 1 MM SCFD, Design Pressure 150 Psig, Design temperature 200 F Includes: Fuel gas scrubber, Electrical Type Fuel gas heater, Fuel gas filter	J-W Gathering Company Froerspm, LA- USA	2011

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
15	Corrisioing Inhibitor Skid	Engineering, procurement, fabrication and supply	Corrosion Inhibitor Skid Include: Corrosion Inhibitor tank, Corrosion Inhibitor pump.	Northen Naturel Gas Morris, IL - USA	2011
16	Incinerator Package	Design selection, procurement & Supply	Incinrator Package For the safe burning of Toxic gases like H2S. Includes: Incinerator with Internally lined refractory, Dual fuel forced draft natural gas Burner to burn the H2S gas and Condensate, Burner management system	Texaco Chemicals Port Arthur, TX - USA	2011
17	JT Skid	Design selection, procurement & Supply	20MMscfd JT skid for removal of heavy hydrocarbons, Design Pressure 1440 psig	Texaco Chemicals Port Arthur, TX - USA	2011
18	Heat Medium Skid	Design selection, procurement & Supply	Heat Medium System Capacity 450 Gallions of Therminol, Design Pressure 150 Psig, Design temperature 400 F. Includes: Helical Coil Heater, Forceed draft Natural gas Burner, Burner Management system, Heat Medium Surge/ expansion tank, Centrifugal type high temperature heat Medium Pumps.	J-W Gathering Company Froerspm, LA- USA	2011
19	Well head Contol	Procurement & Supply	Wellhead control panels (QTY2) Wellhead Manifolds (QTY-4) Chokes (QTY-2).	Methanex Kittimatt, BC - Canada	2012
20	Glycol Dehydration Unit	Design selection, procurement & Supply	Glycol Dehydration 20 MMSCFD capacity. Gas with final outlet moisture content of 5-7 lb of water/ MMSCFD Design Pressure 750 Psig, Design Temperature 200 F. Includes: Bubble cap tray type Glycol absorber,Glycol Flash drum, Glycol reboiler with Direct Fired natural gas burner and honey well controller Burner management system, Plunger type glycol Charger Pumps, Air cooled glycol Exchanger, Doubled pipe type glycol/glycol exchanger, Gas aerial Cooler, Sock and Charcoal Glycol Filters, Gllycol drain tank with level transmitter and submersible pump.	China National Offshore Oil Corp	2012
21	Pig Launcher/ receiver	Design selection, procurement & Supply	Pig launchers/Reciever (QTY-2)	Texaco Chemicals Port Arthur, TX - USA	2012
22	Inlet Compressor	Design selection, procurement & Supply	Intel Compressor. Capacity 45 MMSCFD Gas,Design Pressure 1200 Psig, Inlet pressure 750 psig, discharge pressure 1100psig Design temperature 200 F. Includes: Dresser rand natural gas compressors,Waukesha natural Gas engines, Gas coolers, Oil coolers, Radiators, Suction scrubber,Suction Bottles,Discharge bottles, Compressor after Cooler.	Texaco Chemicals Port Arthur, TX - USA	2012
23	Instrument Air System	Design selection, procurement & Supply	Instrument Air Syatem Capacity 105 SCFM design Pressure 150 Psig, Design temperature 200 F. Includes: Screw type instrument air compressor,Wet air Reciever, Desiccant air dryer, Dry air reciever.	J-W Gathering Company Froerspm, LA- USA	2012

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
24	Fuel Gas Conditioning Skid	Design selection, procurement & Supply	Fuel Gas conditioning Skid Capacity 3 MM SCFD, Design Pressure 200 Psig, Design temperature 200 F Includes: Fuel gas scrubber, Electrical Type Fuel gas heater, Fuel gas filter	Petrochawk Energy Corp Texas,Eagle Ford Shale -USA	2012
25	Heat Medium Skid	Design selection, procurement & Supply	Heat Medium System Capacity 470 Gallions of Therminol, Design Pressure 150 Psig, Design temperature 400 F	NIOC-Petropars Ltd Tombak - Iran	2012
26	JT Refrigeration	Design selection, procurement & Supply	JT refrigeration system. Cpacity 6 MMSCFD Gas, Design Pressure 150 Psig, Design temperature -50 F to 200 F, Includes: Propane Reciever, Propane Economizer, Propane Condenser air cooled type, JT valve, Screw Type Engine Driven, Propane Cpmpressor, Lub Oil Cooler, Suction Scrubber.	Smithfield Energy Cleburne, TX - USA	2012
27	Oil Separator	Design selection, procurement & Supply	Oil Separator. Motor Control Center with Soft Starters, Synchronization Panel for Gensets.	Falcon EDF, Ltd / True Oil, LLC ND/USA	2012
28	Hot oil system	Design selection, procurment, export and commissioning support	Hot Oil System Includes: Hot oil heater with forced draft burner , Hot oil expansions tank, Hot oil circulation pumps, Inlet and Residue Gas metering, Fuel gas Conditioning Skid	Monclova Pirineos Gas SA de CV Mexico	2012
29	Heat Exchanger/separator	Design selection, procurement & Supply	Heat Exchanger and Cold Separator Skid Includes: Plate Fin Heat Exchanger, Cold Separator and Low Temp Separator, J-T Value	Monclova Pirineos Gas SA de CV Mexico	2013
30	Produced water treatment system	Engineering, procurement, fabrication and supply	Produced Water Treatment Package, Skid Mounted, Hydrocylone, IGF, Installation & Pre-Commissioning and Supply	Quanton Resources LLC Jay, FL- USA	2013
31	Bladder	Procurement & Supply	Rubber Bladder Replacement	Spartan	2013
32	Vessels	Design, engineering facrication and supply	Vessels & Tanks: Qty 2 of 48" OD X 10' ASME vessel 300psig and 4 condensate storage tanks of 500bbl each	Lewis Energy Group - USA	2013
33	JT Skids	Design selection, procurment, export and commissioning support	Qty 2 of 20MMSCFD each JT skids with methnol injection system, onskid pumps and pannel	NatGas Mexico	2014
34	Glycol Dehydration Package	Design selection, procurement, refurbishment, export and startup assistance	54" x 30' x 1440 psi – 8 tray glycol tower w/ scrubber – built by Texas Tanque Mfg 1980. Purchased "as-is, where-is", Refurbihsment and export. Along with Refurbished 2000 – 750MMtbu/hr regeneration package, Flash tank – Hanover, Reboiler 1996 Natco, Fire tube new, 450 kimray pumps - rebuilt, Fin tube heat exchanger, shell and tube hair, Peco - 3 canister 1122C carbon filter, Peco - 4 element 336 sock filter, 3 NP nowata filter, 16" still column with shell and tube reflux, flamco flame arrestor burner	Petrojet - Egypt	2014

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
35	JT Skid for HCDP	Design selection and supply of in stock JT skid, export	JT Skid for HCDP - Standard package 30MMscfd - "Brand new/Surplus", 1440PSI, inlcuding methanol injection pumps, on skid panel	Petrojet - Egypt	2014
36	3 Phase Production Separators	Design, Engineering, producrement and export	Quantity 3 of 42" ID X 15' Horizontal 3 phase production seprators, Supply of brand new standard bare vessel with accessories. Providing engineering drawings for packaging on skid at site. These were standard vessel supplied within 10 days of quote.	Petroject - Egypt	2014
37	Compressor Package	Engineering selection and supply of compressor package on "As is, Where is" basis	NGSI Package, Three Stage Compressor Package, design conditions were 0psig suction to 320psig discharge moving a capacity of 3.9mmscfd, MAWP 635 psig, VVCP, Scrubbers #1: 30" X 74" 200psig, Scrubber#2: 24" X 70" 272psig, Scrubber#3: 18" X 66" 272psig. Cooler R&R Model UI-12-24X	Smithfield Energy Cleburne, TX - USA	2014
38	Mechnical Refrigeration Unit	Engineering, procurement "as-is, where-is", dismentalling and export	20MMscfd mechanical refrigeration JT plant. Equipment includes: Demethanizer Mol Sieve Regen Gas system New brazed aluminum exchangers Product surge tank NGL charge pumps NGL pipeline pumps (horizontal centrifugal) Propane refrige skid including chiller, condenser, suction scrubber, and economizer 350 hp propane screw compressor The Plant was in service from 2010-2012 and was disconnected from main cryogenic plant The Client needed some quick solution to stop their discounted gas sale, RAG completed dismentalling and export in 8 weeks of PO, RAG provided dismentalling engineering and hookup drawings with existing gas facility	NatGas Mexico	2015

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
39	Equipment and project material for Gas Processing Plant	Design, Engineering, Procurement and Export	**Flare Stack Package for 30MMSCFD** Flow 65' Guyed Supported Flare stack, Two (2) Pilot(s) with Nema 4X ignition control panels of reach pilot Shipped in less than 30' section (flanged connections) to allow for easy shipment in a 40' container. Upgrade Ignition Enclosure: Enclosures consist of stainless steel construction and meet Class I Div 2 Group C&D using air purge (Z – purge) Two (2) Pilot retraction systems with manual winch, stainless fuel gas line **Fuel Gas Conditioning** package with two trains & fuel gas scrubber OD 16" X 60" S/S 1440 Psig, Flow Rate 1.5 MMscfd **3 Phase separator** 42" Dia, Horizontal ASME sev VIII, Div.1, national board registered, S/S, 1440 PSIG MAWP shipped loose with standard accessories along with 6" gas Meter Run and Flow Transmitter, orifice plate 6"X1/8" X.XXX" 316SS, Cameron Barton NACE Flow recorder Model#202N shipped lose in container and packaged at site **40 MMScfd capacity TEG dehydration unit**, 42" absorber, 1.5 MM btu/hr re-boiler, 48" OD x 270" LG, ASME, packaged with fuel gas scrubber, pump gas separator, Rich/lean glycol exchanger, charcoal filter, glycol sock filter, Kimray pump Supply of various field instruments, valves, F&G detection The client wanted an early first gas date and RAG supplied complete equipment/valves/instruments for the project consisiting of all brand new standard packages in 6 weeks Ex-works Houston	Polish Oil & Gas, Pakistan	2015
40	Separator, Coalescer Filters and HCDP Analyzer	Design, Engineering, Supply and Commissioning	3 Phase separator 78 (ID) In X 19.5 (T/T) ft, Horizontal ASME Sev VIII, Div.1, Two Coalescer Filters 26 (ID) In X 8.6 (F/T) ft. Civil works, foundation, Erection, installation, commissioning, Hydro test, RT, Leakage test, instrumentation, Electrical works, on field cable trays & cables laying. Integration of package instruments signals with Allen Bradley PLC and Main CCR Honey well system through hardwire and mod buses.	Foundation Power - Daharki - Pakistan	2016
41	3 phase separators	Design, Engineering, Procurement and Export	Supply of quantity 2 of 30"OD X 10', 3 Phase Horizontal ASME sev VIII, Div.1, national board registered, S/S, 1440 PSIG vessel along with standard accessories	Petrojet - Egypt	2016

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
42	O2 Removal Packag	Design, Engineering, Procurement, export and commissioing assistance	10MMscfd, Quantity 2 of 5MMscfd each membrane skid bank for removal of 17% CO2 to pipeline specifications	Quanton Resources LLC Jay, FL- USA	2016
43	Generators	Selection, Procurement, Refurbishment, supply and installation	2 x CAT 1025 kW Diesel Generator Sets 1025 kW Continuous CAT 3512 Engines Kato 480V Generator ends Aprox 650 Hrs total (original) on each one since new Open Skid mounted (no tank/ no mufflers) Complete, with attached Radiator	Smithfield Energy Cleburne, TX - USA	2016
44	Flare Stack Package	Design, Engineering, Procurement and Export	30MMscfd, Skid mounted, Guy-supported Flare Stac 3 multi-jet flare tips, HSLF Pilot w/type K thermocoupl Retractable polit components, Automatic ignition ai	Petrojet - Egypt	2016
45	Amine cooler	Design selection, procurement and export	Amine cooler 220V/3phz/50HZ,1500 rpm with NEMA motors	Petrojet - Egypt	2016
46	Generators	Selection, procurement and export	Supply of Qty 2 of CAT G3512 gas generators 1000eKW@0.8 PF, Fuel Natural Gas	Petrojet - Egypt	2016
47	Line Heater	Design selection, procurement, refurbishment and export	2.0 MM line heater, mobile, mounted on trailer	NatGas Mexico	2016
48	Design/Engineering	Detail Engineering	Located outside of Grande Prairie Alberta, this project involved the installation of a facility designed to process and stabilize 3,498 m3/day (22,000 bpd) of sour emulsion. The emulsion contained 2,226 m3/day (14,000 bpd) of raw condensate and 1,272 m3/day (8,000 bpd) of produced water with up to 8% H2S. The raw condensate was separated from the water, stabilized, and pumped to Pembina's Peace Pipeline system. A Mercaptan Removal Unit (MRU) was required to reduce the remaining sulfur species (mercaptans) in the stabilized condensate. The produced water was pumped to a water injection well site. Any flashed gas and overheads from the stabilizer were compressed, blended with sweet gas from TCPL, and pipelined to a separate facility for final processing. RAG scope of work included tank design, civil, mechnical, electrical, piping desing, isometric and 3D model, plot plan	Devon Energy Corporation Delaware USA	2016
49	3 Phase Separator	Design selection, Supply and export	Supply of 36"ID X 10' 2 phase horizontal separator	Petrojet - Egypt	2017

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
50	Spares	Procurement & Export	Supply of various spares for 20 MMscfd Mechnical Refrigeration Package including two years operating spares for complete MRU	NatGas Mexico	2017
51	Regulatory/Engineering	Engineering/Regulatory Permitting	Exxon lead partner of consortium consisting of Qatar petroleum, Mitsubishi, Total and GEI. Consortium was putting a LNG terminal of 1000 MMSCFD at port Qasim Karachi. Our scope of work was to review/obtain all permits of departments involved including OGRA, SSGC, Ministry, PQA and other federal & provincial departments. Departmental approval of permits & plan approval from departments and their review to be incorporated in feed design.	Exxon Mobil - USA	2017
52	Condensate Stablization Package	Design selection, Supply and export	Condensate Stablization Package - "Brand New/Surplus" 17" Stabilizer ships as two skids, an exchanger skid and a tower skid The exchanger skid is 8'W x 35' L and the column skid is 8' W x 10' L x 33' H	Dubri Oil - Nigeria	2017
53	JT Skid for HCDP	Design selection, Supply and export	30MMSCFD JT SKID, DESIGN PRESSURE 1440PSI With two BEM S/T heat exchangers in series that exchange process gas with inlet gas, a two phase separator, on-skid instrument gas system and a methanol injection system	Dubri Oil - Nigeria	2017
54	TEG Dehydration Coloumn	Design selection, Supply and export	42" ID standard ASME tower with bubble cap trays and man hole	Dubri Oil - Nigeria	2017
55	Condensate Stablization Package	Design selection, Supply and export	2MMbtu reboiler with 42"OD tower - new surplus	Citla Energy - Mexico	2017
56	FEED/Engineering	Engineering	Process Design for 40MMscfd gas facility having production seprator, Dehydration, 220GPM amine sweetning and detail engineering design including piping, civil, mechnical, electrical and I&C	G&F Oil Company Inc - TX	2017
57	3 Phase separator	Design selection, Supply and export	36"ODX10' 3 phase horizontal seprator 1440psi with ship loose accessories	G&F Oil Company Inc - TX	2017
58	Inlet Air cooler	Design selection, Supply and export	Inlet Air cooler "Brand new" AXH Model#93AZF (218066)	Petrojet Egypt	2018
59	3 Phase Production Separators	Design selection, Supply and export	48" OD 3 phase production separator, horizontal, skid mounted with oil, water meter, 6" inlet out let connections, 1440psig	Rife Energy Operating - TX	2018
60	Metering Skid	Design selection, Supply and export	20MMscfd, 1440 psi, operating temperature 80-120F W one primary meter tube w/senior oriice Fitting, moisture analyzer Sample conditioning system, HCDP analzer, AGA – 3 GC and Flow computer	Dubri Oil - Nigeria	2018

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
61	Amine Contactor	Design, fabrication Installation and commissioning	Design, fabrication, U-Stamping /Inspection, Ceramic coating, installation and commissioning of Amine Stripper & Reflux Accumulator. size: ID=4', Height: 46'-10",	Dewan Petroleum - Pakistan	2018
62	Compression Package	Design, Procurement, Rearrangement/repackaging and export	Design, Procurement, Repackaging, Recertification of used compressor package and suction/discharge vessels with brand new coolers. Flow 40MMscfd, SP 200 psi, DP 1100psi. The old compression skid was stripped down to bare skid, sandblasted/painted, new control pannel, Recertified PSVs, Zero hour engine overhaul, zero hour compressor overhaul, new skid piping, vessels hydrotesting and recertification, change of name plates, packing and export	Monclova Pirineos Gas SA de CV Mexico	2018
63	Produced Water Reinjection Facility	Engineering, Supply, Installation & Commissioning	Modification of produced water reinjection Facility at wellhead. Capacity: 5000 BPD Water injection Pressure: 5000 Psi including civil, mechanical works, installation and startup.	MOL Pakistan Oil & Gas B.V	2018
64	Loading and Discharge Compression	FEED & Engineering	9.5 MMSCFD natural gas compression from suction pressure of 150 psi to 3000 psi, design of mother and daugther compression station, gas dryer, utilities, civil, mechnical, electrical design, heat exchangers and design/procedures for efficient loading/unloading and supply chain management through high pressure gas transport carriers	Cimarex Energy Co.	2018
65	Natural Gas Processing and Liquification	FEED & Feasibility report	FrontEnd Engineering design and consulting for development of feasibility and RFQs for 20MMscfd natural gas liquification facility. The SOW included design of surface facility, amine sweetning unit to reduce 17% CO2 to less than 1%	Devon Energy Corporation	2019
66	Mechnical Refrigeration Unit	Engineering, procurment and export	Mechanical Refrigeration Package - 35MMscfd - Exterran 2012 manufactured, surplus never used unit. Sales of plant as is, where is and export. Equipment List included: Qty 2 of Gas/Gas Exchangers, Stablizer Feed/Bottom Exchanger, Chiller, Stablizer Reboiler, Glycol Reboiler, Glycol/Glycol exchanger, Lube oil cooler Qty 3, Refrigerent Condenser, cold separator, Refrigerent Accumulator, Refrigerent Economizer, Refrigerent suction scrubber, Refrigerent Reclaimer, Glycol Flash tank, Glycol filter, Glycol Charcoal Filter, Hot oil surge tank, Stablizer, packing, internals, hot oil & glycol pumps, Qty 3 of refrigeration compressors and hot oil heater	Dubri Petroleum - Nigeria	2019
67	LPG Extraction	Engineering & Procurement Assistance	Process design, Engineering and development of RFQs for the procurment and subcontracting of 40Ton per day LPG extraction facility, offsites and residential block	Dubri Petroleum - Nigeria	2019

Sr No.	Equipment	Scope of Work	Description	Client/location	Year
68	TEG Dehydration Unit	Engineering, Fabrication and supply	Engineering, fabrication mnaagement and supply of 750mmbtu/hr reboiler and 42" verticle coloumn. TEG Dehydration Package	Devon Energy Corporation	2019
69	Compression Package	Engineering selection, procurement, supply, commissioning assistance and startup	Supply of surplus brand new Compression Package with Arial Compressor and CAT Engine to handle suction from 150psig to discharge at 1200psig for 30MMscfd gas along with suction and discharge bottle, complete electrical connections with onskid pannel ready to hook at site	Cumming Co. Inc. Forthworth TX	2019
70	Trailer Mounted 3 phase test separator	Design selection, procurement and supply	42" OD, 1440psig trailer mounted 3 phase test separator with water/oil/gas measuring meter, chart recorder, level controllers and sampling system	Rife Energy Operating - TX	2020
71	Air Coolers	Engineering, procurement, export, commissioning and startup	Amine Cooler, Reflux Cooler and Gas Cooler for Amine sweetning unit with flame proof/ explosion proof motors	Petroleum Exploration - Pakistan	2020
72	EPCM	FEED, Detail Engineering, Procurement, Construction Management	FEED and Detail Design for a sour gas plant with process trains (2 x 60 MMscfd) containing inlet separation, inlet/sales compression (4 reciprocating compressors totaling 15,000 hp), amine sweetening (CO_2 and H_2S removal), refrigeration, liquid fractionation and stabilization, acid gas compression, vapour recovery, recycle system, power generation (2 x 4.6 MW gensets), storage for produced water, condensate (275 bpd) and NGL (171 bpd) with truck-out facility. Prepration and evaluation of RFQs, Construction management and commissioning	Devon Energy Corporation - Delaware Basin	2020
73	H2S Removal	Engineering, procurment and export	H2S Removal package, 10MMscfd, chemical injcetion, skid mounted with pumps, heat exchanger, chemical dosing tanks, onskid instrumentation, wiring and pannel	NatGas Mexico	2020
74	Mechanical Refrigeration Unit	Design selection, procurment, dismantalling and export	Mechanical Refrigeration Package - 35MMscfd - Exterran manufactured, used unit. Sales of plant as is, where is and export. Equipment List included: Qty 2 of Gas/Gas Exchangers, Stablizer Feed/Bottom Exchanger, Chiller, Stablizer Reboiler, Glycol Reboiler, Glycol/Glycol exchanger, Lube oil cooler Qty 3, Refrigerent Condenser, cold separator, Refrigerent Accumulator, Refrigerent Economizer, Refrigerent suction scrubber, Refrigerent Reclaimer, Glycol Flash tank, Glycol filter, Glycol Charcoal Filter, Hot oil surge tank, Stablizer, packing, internals, hot oil & glycol pumps, Qty 3 of refrigeration compressors and hot oil heater	Petroleum Exploration - Pakistan	2021
75	Compression Package	Design selection, procurement & Supply	Sale of surplus compressor as is where is basis Waukesha 7042GSI ESM Ariel JGK/4-3 Stage. 2 - 14.125 1st stage cylinders 1 - 11.00 2nd stage cylinder 1 - 7.875 3rd stage cylinder 156 Harsco Air X Changer cooler	G&F Oil Company Inc. Texas	2021

Pictures Gallery

NatGas Mexico
Mechanical Refrigeration Unit

Pictures Gallery

Glycol Dehydration Package
Petrojet - Egypt

JT Skid for HCDP
Petrojet - Egypt

3 Phase Production Separators
Petrojet - Egypt

Compressor Package
Smithfield Energy Cleburne, TX - USA

Natural Gas Compressor Control Panel
Smithfield Energy Cleburne, TX - USA

Mechanical Refregeration Unit
Cumming Co,Inc.

Pictures Gallery

Gas Train With Project Material
Polish Oil & Gas, Pakistan

Pictures Gallery

Installation & Construction of Separator, Coalescer Filters and HCDP Analyzer
Jereh - Pakistan

Pictures Gallery

JT Skid for HCDP
Dubri Oil - Nigeria

JT Skid for HCDP
Dubri Oil - Nigeria

Amine cooler
Petrojet - Egypt

Line Heater
NatGas Maxico

3 Phase Separator
Petrojet - Egypt

Natural Gas Generators
Smithfield Energy Cleburne, TX - USA

Pictures Gallery

TEG Dehydration Coloumn
Dubri Oil - Nigeria

Condensate Stablization Package
Citla Energy - Mexico

Inlet Air cooler
Petrojet - Egypt

3 Phase Production Separators
Rife Energy Operating - TX

Amine Contactor
Dewan Petroleum - Pakistan

Pictures Gallery

Compression Package
Monclova Pirineos Gas SA de CV Mexico

Pictures Gallery

Mechnical Refrigeration Unit
Dubri Petroleum - Nigeria

Pictures Gallery

TEG Dehydration Unit
Devon Energy Corporation

Compression Package
Cumming Co. Inc. Forthworth TX

Pictures Gallery

Air Coolers
Petroleum Exploration - Pakistan

Pictures Gallery

EPCM
Rife Energy Operating Texas - USA

EPCM
Devon Energy Corporation Delaware - USA

Pictures Gallery

Compression Package
G&F Oil Company Inc. Texas

Produced Water Re-injection Facility
MOL Pakistan Oil & Gas B.V

Picture Gallery

Mechanical Refrigeration Unit
Petroleum Exploration - Pakistan

Picture Gallery